


Note B:
Station for light post support bracket shown on Plans is only approximate. Φ Bracket to be located midway between parapet control joints.
A = Normal parapet control joint spacing (adjust as necessary to meet minimum limitations).
If a light post is placed at Φ of pier, eliminate the control joint at the Φ of pier. The first control joint beyond, on one side only shall be changed to a paraffin joint.



SECTION A-A
Scale: 1/2"=1'-0"

Note:
Deck overhang reinforcing steel not shown.

Note A:
Contractor is to contact the District Engineer in writing prior to placing sleeves for anchor bolts, to ascertain the bolt circle dimension and size of anchor bolts that will be used on this project. All light poles to be set plumb using leveling nuts on anchor bolts. Max. height of pole for this detail is 40'.

For Section "B-B" see Sheet 2 of 2.

SIDEWALK WITH STRAIGHT BACK

| APPROVAL | |
|------------------------------|----------|
| <i>E. S. Friedman</i> | DIRECTOR |
| OFFICE OF BRIDGE DEVELOPMENT | |
| DATE: 6/11/05 | |
| REVISIONS | |
| SHA | FHWA |
| 10-9-07 | |
| 1-9-08 | |
| FHWA APPROVAL | |
| DATE: | |

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT



SUPPORT BRACKET FOR BRIDGE MOUNTED LIGHT POST
WITH SINGLE CONDUIT AND PARAPET
WITH STRAIGHT BACK AND SIDEWALK

STANDARD NO. BR-SS(6.5I)-05-353(L)

SHEET 1 OF 2

SUPER-CONCRETE WORK